(3) Suitable dust proof ventilators should be provided for in the roofing.

(4) The roofing shall be flat with two man-hole covers each 3′×3′ complete with mild steel lids, hinges, hasp and staple suitable for locking.

(5) One water level indicator complete with float gauge board pointer, flexible wire, guide pulleys, etc., shall be included in the tender.

(6) The outer surface of the side wall except the roofing and inside of the parapet should be finished with cream-coloured cement.

(7) *Nature of foundation.*—Gravel, with boulder out crops.

(8) All the pipe fittings will be supplied by the Department.

(9) A small parapet to the tank of suitable design should be provided for in the tender.

(10) No lumpsum quotations will be considered. Plans and estimates with detail drawings showing various reinforcements should accompany the tender. The estimate should give the quantities, rates and cost of each item. Any variation in the quantity will be paid for at the rates as per the detail estimate.

(11) Non-tendered items of work will be paid for after working out the data with not more than 10 per cent profit for the contractor.

(12) Cement to be used should be purchased through the Department.

M. K. NARASIMHA IYER,
Executive Engineer.

BANGALORE DIVISION.

Abstract Notification dated 24th February 1940.

The attention of the public is hereby invited to the detailed notification inviting sealed tenders for restoring Kayamgutta Kattariguppe Kannerkatte Minor Tank, Reg. No. 62 of Bangalore Taluk, published on pages 428-430, Part VI of the *Mysore Gazette*, dated 29th February 1940.

The last date for the receipt of the tender is 2 P.M. on 16th March 1940. Duplicate chellan for having credited the deposit amount of Rs. 210 into the Treasury under "17 (*a*) P. W. Deposits" should accompany each tender.

Abstract Notification dated 24th February 1940.

The attention of the public is hereby invited to the detailed notification inviting sealed tenders for restoring Dandidass Kodagehalli Tank, Reg. No. 192 of Dodballapur Taluk, published in pages 430-432, Part VI of the *Mysore Gazette*, dated 29th February 1940.

The last date for the receipt of the tender is 2 P.M. on 18th March 1940. Duplicate chellan for having credited the deposit amount of Rs. 300 into the Treasury under "17-(*a*) P. W. Deposits" should accompany each tender.

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

BUREAU OF SANITARY ENGINEERING, BANGALORE.

Abstract Notice dated 5th March 1940.

The attention of the public is invited to the notification calling for tenders for the work of "Providing Sanitary fittings in the newly constructed latrine attached to the Agricultural Office, Bangalore," published in Part VI, pages 522-524 of the *Mysore Gazette*, dated 7th March 1940.

The last date of receiving tenders is fixed on 18th March 1940.

Notification dated 4th March 1940.

Notice is hereby given that sealed tenders will be received at the Office of the Sanitary Engineer, Bureau of Sanitary Engineering, Bangalore, up to 1 P.M. on 19th March 1940, for the drainage work of the mode moats around the fort in Periyapatna Town to prevent breading of mosquitoes. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1940.

2. The plans, detailed estimate and conditions may be seen at the Sanitary Engineer's Office between the hours of 11 A.M. and 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Sanitary Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 150 in cash (no cheques will be accepted) as earnest money, and be superscribed "Tender for the drainage work of the mode moats around the fort in Periyapatna Town to prevent breading of mosquitoes in default of which the tenders will be rejected.

5. The final acceptance of the tender will rest with the Director of Public Health, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Sanitary Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Sanitary Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Sanitary Engineer will be final and legally binding.

Estimate for the approximate quantities for the drainage of moats around the fort in Periyapatna to prevent breeding of mosquitoes.

No.	Particulars	Unit	Quantity
1	Jungle clearing including removing of roots, etc., complete	Sq.yd.	31,991
2	Earthwork cutting and filling to depressions including a lead of one furlong	C.yd.	10,806
	CONSTRUCTION OF TUNNEL.		
3	Pitching with available boulders for the bed of the tunnel after conveyance	C.yd.	7
4	Construction of abutments with available stones in clay cut to required sizes including dismantling and conveying charges	C.ft.	333
5	Cement pointing the abutments	Sqr.	2·22
6	Covering the tunnel with 6" B.S. slabs, edges dressed and fixed	S.ft.	259
7	Cushion earth over tunnel	C.yd.	23
8	Rough stone revetment for wings (with available stones)	,,	18
9	Constructing body wall with available stones in chunam mortar and joints pointed with cement	C.ft	375
10	Rough stone apron with available stones	C.yd.	9

K. S. HUTCHA RAO,
Sanitary Engineer.

KOLAR DIVISION.

Notification dated 30th January 1940.

1. Sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. on 30th March 1940, for restoring Sulur Keggere Tank (unrestored minor) Reg. No. 214/743 in Kolar Taluk.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Kolar Division, should be addressed to the Executive Engineer, Kolar Division, in a sealed cover and superscribed as "Tender for restoring Sulur Keggere Tank (unrestored minor). The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a treasury chellan for earnest money of Rs. 225 paid to the treasury to the credit of "17 (*a*) P. W. Deposits" against the account of the Executive Engineer, Kolar Division. The earnest money of the successful tenderer will be retained as security for the due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 30th March 1940 at Kolar. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.